

**Sant Longowal Institute of Engineering and Technology,
Longowal, Distt. Sangrur
(Deemed to be University)
(Established by Govt. of India)**

Quotation Notice

Quotation are invited from working contractors registered with CPWD, State PWD, MES, PUDA/Central Public Sector undertaking having valid license under Contractor Labour (Regulation & Abolition) Act, 1970 and experience of having successfully completed works during the last 7 years ending last day of the month previously to one in which applications are invited:

Three similar completed work each costing not less than the amount equal to 40% of estimated cost put to tender or Two similar completed works, each costing not less than the amount equal to 60% of the estimated cost put to tender or One similar completed work of costing not less than the amount equal to 80% of the estimated cost put to tender with some Central Government Department/State Government Department/Central Autonomous Body/Central Public Sector undertaking.

Sr. No.	Name of Work	DNIT Amount (Rs. In Rupees)	Earnest Money Deposit is 2% of the DNIT amount (Rs. in Rupees)	Cost of Quotation Documents in (Non-refundable)	Time Period	Tender processing fee (Rs.)	Schedule of Quantities
1	Re-installation of existing sign board at intersection of main highway and road to Duggan by providing new RCC foundation, repainting, fixing new retro reflective sheet including writing the name of Institute	45,897.00	Nil	Nil	45 Days	Nil	Annexure- 'A'

The Quotation documents will be available only on the Institute's website and should be submitted in the estate office (Civil Wing).

Schedule of Quotations

Availability of Quotation for Bidding		Last date of Submission of Quotation	Date and time of opening of Quotation in Estate Office, SLIET, Longowal
From	To		
16.03.2017	22.03.2018	22.03.2018 before 5:00 PM	23.03.2018 at 12: 30 PM

Eng.-In-Charge

Annexure- 'A'

Name of Work: Re-installation of existing sign board at intersection of main highway and road to Duggan by providing new RCC foundation, repainting, fixing new retro reflective sheet including writing the name of Institute.

S.No.	DESCRIPTION OF ITEM	UNIT	QTY.	RATE	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	Cum	2.50		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III): 6 graded stone aggregate 40 mm nominal size)	Cum	0.15		
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size).	Cum	1.65		
4	Centering and shuttering including strutting, propping etc. and removal of form for all heights : 5.9.1 Foundations, footings, bases of columns, etc. for mass concrete	Sqm	8.00		
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Cold twisted bars.	Kg	59.00		
6	Providing and fixing bolts including nuts and washers complete.	Kg	12.50		
7	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	Sqm	15.00		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	15.00		
9	Removing Old retro reflective sheet and Refixing new retro reflective sheet including writing the name of the Institute on existing road sign board complete as per direction of Engineer-in charge.	Sqm	10.00		
10	Hoisting & fixing in position of existing MS road sign board (weight 600 Kg) of SLIET by special mechanical device at intersection of main highway & road towards Duggan Village complete in all respect as per directions of Engineer-in-charge. Including transportation of SLIET to place of installation at main highway.	Job	1.00		
				Total Rs.	

Eng.-In-Charge