

**Sant Longowal Institute of Engineering and Technology,
Longowal, Distt. Sangrur
(Deemed to be University)
(Established by Govt. of India)**

Quotation Notice

Quotation are invited from working contractors registered with CPWD, State PWD, MES, PUDA/Central Public Sector undertaking having valid license under Contractor Labour (Regulation & Abolition) Act, 1970 and experience of having successfully completed works during the last 7 years ending last day of the month previously to one in which applications are invited:

Three similar completed work each costing not less than the amount equal to 40% of estimated cost put to tender or Two similar completed works, each costing not less than the amount equal to 60% of the estimated cost put to tender or One similar completed work of costing not less than the amount equal to 80% of the estimated cost put to tender with some Central Government Department/State Government Department/Central Autonomous Body/Central Public Sector undertaking.

Sr. No.	Name of Work	DNIT Amount (Rs. In Rupees)	Earnest Money Deposit is 2% of the DNIT amount (Rs. in Rupees)	Cost of Quotation Documents in (Non-refundable)	Time Period	Tender processing fee (Rs.)	Schedule of Quantities
1	Repair and Maintenance/ Standerdization of classrooms (Civil Work) L-6 (Science Block) at SLIET, Longowal	60,494.00	Nil	Nil	01 Month	Nil	Annexure- 'A'

The Quotation documents will be available only on the Institute's website and should be submitted in the estate office (Civil Wing).

Schedule of Quotations

Availability of Quotation for Bidding		Last date of Submission of Quotation	Date and time of opening of Quotation in Estate Office, SLIET, Longowal
From	To		
16.05.2018	23.05.2018	23.05.2018 before 5:00 PM	24.05.2018 at 12: 30 PM


Contractor


Eng.-In-Charge

**Name of Work: Repair and Maintenance / Standerdization of classrooms (Civil Work) L-6 (Science Block) at SLIET,
Longowal**

S.No.	DESCRIPTION OF ITEM	UNIT	QTY.	RATE	AMOUNT
1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	Sqm	185.00		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer , over the plastered wall surface to prepare the surface even and smooth complete	Sqm	185.00		
3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. Complete	Sqm	185.00		
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm	350.00		
5	Providing & laying black film on glasses of windows etc. All complete as per direction of Engineer-in-charge.	Sqm	25.00		
-				Total Rs.	

Contractor


Eng.-In-Charge