

**Sant Longowal Institute of Engineering and Technology,
Longowal, Distt. Sangrur
(Deemed to be University)
(Established by Govt. of India)**

Quotation Notice

Quotation are invited from working contractors registered with CPWD, State PWD, MES, PUDA/Central Public Sector undertaking having valid license under Contractor Labour (Regulation & Abolition) Act, 1970 and experience of having successfully completed works during the last 7 years ending last day of the month previously to one in which applications are invited:

Three similar completed work each costing not less than the amount equal to 40% of estimated cost put to tender or Two similar completed works, each costing not less than the amount equal to 60% of the estimated cost put to tender or One similar completed work of costing not less than the amount equal to 80% of the estimated cost put to tender with some Central Government Department/State Government Department/Central Autonomous Body/Central Public Sector undertaking.

Sr. No.	Name of Work	DNIQ Amount (Rs. In Rupees)	Earnest Money Deposit is 2% of the DNIQ amount (Rs. in Rupees)	Cost of Quotation Documents in (Non-refundable)	Time Period	Quotation processing fee (Rs.)	Schedule of Quantities
1	Raising the walls of Boys Hostel No. 7 & 8 (Mess Area) at SLIET, Longowal	43,775.00	Nil	Nil	One Month	Nil	Annexure- 'A'

The Quotation documents will be available only on the Institute's website and should be submitted in the estate office (Civil Wing).

Schedule of Quotations

Availability of Quotation for Bidding		Last date of Submission of Quotation	Date and time of opening of Quotation in Estate Office, SLIET, Longowal
From	To		
29/11/2018	06/11/2018	06/11/2018 upto 5PM.	07/11/2018 at 11:00 AM.

Contractor


[Signature]
Eng.-In-Charge

Annexure- 'A'

Name of Work: Raising the walls of Boys Hostel No. 7 & 8 (Mess Area) at SLIET, Longowal,

S.No.	DESCRIPTION OF ITEM	UNIT	QTY.	RATE	AMOUNT
1	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	Sqm.	3.50		
2	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like	Sqm.	0.50		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum.	3.00		
4	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg.	300.00		
5	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	Sqm.	15.00		
6	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm.	75.00		
				Total Rs.	

Contractor


 Eng.-In-Charge
